



Saddle Mount Detail

• 0.063" aluminum skin and 2.0" x 2.0" aluminum frame



WIND DESIGN CRITERIA	
WIND VELOCITY	132 MPH
RISK CATEGORY	II
EXPOSURE CATEGORY (MMRF)	C
INTERNAL PRESSURE COEFFICIENT	+0
COMPONENT & CLADDING PRESSURES	36.8 PSF
FORCE COEFFICIENT	1.7

1. Design wind pressure in conformance w/ FBC-2017 Ed Ref. ASCE7. See chart for design criteria per ASCE 7-10.
- 2a. EFIS Wall Attachment:
ASTM A307 3/8" x 3" Hilti togglers fastened into Stucco over plywood fascia, top and bottom as per detail.
- 2b. CMU Wall Attachment:
3/8" x 3" fully embedded Tapcon anchors top and bottom as per detail.



COMPANY:

TAYLOR
Sign & Design, Inc.
COMMERCIAL SIGN TECHNOLOGIES
State Certified # ES12000117
www.TaylorSignCo.com

4162 St. Augustine Rd. Jacksonville, FL 32207
Phone: 904/396 4652 • Fax 904/396-3777

SAN MARCO CHURCH

CONTACT: Steve Painter
PHONE 904-553-3250
EMAIL steve.painter@comcast.net
ADDRESS: 1620 Naldo Ave
Jacksonville, FL 32207

DATE: 12/10/19

REVISIONS: R1-12/11/19
R2-12/12/19

SALES PERSON: Chris Taylor
DESIGNER: Guy Browning
ZONING: RMD-D
50 sq ft max
12 ft ht max

SAVED AS: San Marco Church - Monument

This artwork protected under copyright law and is the property of Taylor Sign & Design, Inc. And is not to be duplicated, reproduced, or distributed without written permission.
©2018 Taylor Sign & Design, Inc
This sign meets or exceeds 132 mph wind zone requirements as per 2017 Florida Building Code.

PLEASE ENSURE ALL COLORS, DIMENSIONS, VERBIAGE, LAYOUT, ETC. ARE CORRECT BEFORE APPROVING RENDERING. COLORS PORTRAYED ON PROOF MAY NOT MATCH FINAL PRODUCT DUE TO THE DIFFERENCE BETWEEN DIGITAL AND PIGMENTED COLORS. ONCE ARTWORK IS APPROVED YOU WILL BE RESPONSIBLE FOR 1/2 THE RE-MAKE COST SHOULD ANY PROBLEMS BE FOUND AFTER INSTALLATION.

APPROVED BY _____

DATE _____